

AD-A272 844



12
CR 93.004

NCEL

August 1993

An Investigation Conducted by
Battelle

Columbus, Ohio and

Contract Report

the Naval Civil Engineering Laboratory

FIELD DEMONSTRATION OF A SIEVING AND STABILIZATION TECHNOLOGY ON LEAD-CONTAMINATED SOILS AT A SMALL ARMS RANGE - MAYPORT NAVAL AIR STATION

Abstract One source of environmental heavy metal contamination is impact berms at small ranges. Soils used to capture the bullets can accumulate lead in excess of the RCRA hazardous waste limits. This report describes a method to recover and recycle the lead bullets screened from the soil and to treat the soil to reduce the leachability of the remaining lead contamination. A field demonstration using a stabilization process based on a soluble silicate and cement formulation was conducted to evaluate the chemical effectiveness of this technology and the ability to reuse the stabilized soil to capture bullets in the impact berm.

S DTIC
ELECTE
NOV 18 1993
A

93-28299



NAVAL CIVIL ENGINEERING LABORATORY PORT HUENEME CALIFORNIA 93043-4328

Approved for public release; distribution is unlimited.

93 11 17 020

METRIC CONVERSION FACTORS


Approximate Conversions to Metric Measures

Symbol	When You Know	Multiply by	To Find	Symbol
LENGTH				
in	inches	2.5	centimeters	cm
ft	feet	30	centimeters	cm
yd	yards	0.9	meters	m
mi	miles	1.6	kilometers	km
AREA				
in ²	square inches	6.5	square centimeters	cm ²
ft ²	square feet	0.09	square meters	m ²
yd ²	square yards	0.8	square meters	m ²
mi ²	square miles	2.6	square kilometers	km ²
	acres	0.4	hectares	ha
MASS (weight)				
oz	ounces	28	grams	g
lb	pounds	0.45	kilograms	kg
	short tons (2,000 lb)	0.9	tonnes	t
VOLUME				
teaspoons	teaspoons	5	milliliters	ml
fluid ounces	fluid ounces	15	milliliters	ml
cups	cups	30	milliliters	ml
pints	pints	0.24	liters	l
quarts	quarts	0.47	liters	l
gallons	gallons	0.95	liters	l
cubic feet	cubic feet	3.8	liters	l
cubic yard	cubic yard	0.03	cubic meters	m ³
		0.76	cubic meters	m ³
TEMPERATURE (exact)				
°F	Fahrenheit temperature	5/9 (after subtracting 32)	Celsius temperature	°C

*1 in. = 2.54 (exact). For other exact conversions and more detailed tables, see NIST Metric Table 286, Units of Weights and Measures, Price \$2.25, SO (reading No. C13.10.286).

Approximate Conversions from Metric Measures

Symbol	When You Know	Multiply by	To Find	Symbol
LENGTH				
mm	millimeters	0.04	inches	in
cm	centimeters	0.4	inches	in
m	meters	3.3	feet	ft
m	meters	1.1	yards	yd
km	kilometers	0.6	miles	mi
AREA				
cm ²	square centimeters	0.16	square inches	in ²
m ²	square meters	1.2	square yards	yd ²
km ²	square kilometers	0.4	square miles	mi ²
ha	hectares (10,000 m ²)	2.5	acres	
MASS (weight)				
g	grams	0.035	ounces	oz
kg	kilograms	2.2	pounds	lb
t	tonnes (1,000 kg)	1.1	short tons	
VOLUME				
ml	milliliters	0.03	fluid ounces	fl oz
l	liters	2.1	pints	pt
l	liters	1.06	quarts	qt
l	liters	0.26	gallons	gal
m ³	cubic meters	35	cubic feet	ft ³
m ³	cubic meters	1.3	cubic yards	yd ³
TEMPERATURE (exact)				
°C	Celsius temperature	9/5 (then add 32)	Fahrenheit temperature	°F



REPORT DOCUMENTATION PAGE			Form Approved OMB No. 0704-0188	
<p>Public reporting burden for this collection of information is estimated to average 1 hour per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to Washington Headquarters Services, Directorate for Information and Reports, 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 22202-4302, and to the Office of Management and Budget, Paperwork Reduction Project (0704-0188), Washington, DC 20503.</p>				
1. AGENCY USE ONLY (Leave blank)		2. REPORT DATE August 1993		3. REPORT TYPE AND DATES COVERED Final; February 1990 thru February 1991
4. TITLE AND SUBTITLE FIELD DEMONSTRATION OF A SIEVING AND STABILIZATION TECHNOLOGY ON LEAD- CONTAMINATED SOILS AT A SMALL ARMS RANGE AT MAYPORT NAVAL AIR STATION			5. FUNDING NUMBERS PR - Y0817-004-71-093 TA - 90-537	
6. AUTHOR(S) G. L. Headington, J. L. Means, G. Meyer, B. Nelson,* and J. C. Heath*				
7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES) Battelle 505 King Avenue Columbus, OH 43201			8. PERFORMING ORGANIZATION REPORT NUMBER CR 93.004	
9. SPONSORING/MONITORING AGENCY NAME(S) AND ADDRESS(ES) Commander / Naval Civil Engineering Laboratory Naval Station Mayport Environmental Restoration and Mayport, FL 32228-0067 Utilities Division/Code L71 Port Hueneme, CA 93043-4328			10. SPONSORING/MONITORING AGENCY REPORT NUMBER	
11. SUPPLEMENTARY NOTES *B. Nelson and J. C. Heath are with the Naval Civil Engineering Laboratory.				
12a. DISTRIBUTION/AVAILABILITY STATEMENT Approved for public release; distribution is unlimited.			12b. DISTRIBUTION CODE	
13. ABSTRACT (Maximum 200 words) One source of environmental heavy metal contamination is impact berms at small arms ranges. Soils used to capture the bullets can accumulate lead in excess of the RCRA hazardous waste limits. This report describes a method to recover and recycle the lead bullets screened from the soil and to treat the soil to reduce the leachability of the remaining lead contamination. A field demonstration using a stabilization process based on a soluble silicate and cement formulation was conducted to evaluate the chemical effectiveness of this technology and the ability to reuse the stabilized soil to capture bullets in the impact berm.				
14. SUBJECT TERMS Stabilization, rifle ranges, small arms ranges, lead, heavy metals, chemical fixation stabilization			15. NUMBER OF PAGES 20	
			16. PRICE CODE	
17. SECURITY CLASSIFICATION OF REPORT Unclassified	18. SECURITY CLASSIFICATION OF THIS PAGE Unclassified	19. SECURITY CLASSIFICATION OF ABSTRACT Unclassified	20. LIMITATION OF ABSTRACT UL	

TABLE OF CONTENTS

	<u>Page</u>
1.0 INTRODUCTION	1
2.0 SAMPLING AND ANALYSIS PROGRAM	2
3.0 TREATABILITY STUDY	4
4.0 FIELD DEMONSTRATION	6
4.1 Initial Soil Sampling	6
4.2 Pilot Test Preparation	6
4.3 Pilot Tests	11
4.4 Full-Scale Treatment	13
5.0 DISCUSSION AND CONCLUSIONS	15
5.1 Treatment Cost Analysis	15
5.2 Process Effectiveness	15
5.3 Future Sampling	16

LIST OF TABLES

TABLE 1. BENCH-SCALE TEST DATA	5
TABLE 2. CHARACTERIZATION OF UNTREATED SOIL BERM FOR Pb, Cu, AND Zn	7
TABLE 3. TREATABILITY DATA ON PILOT TEST RUNS NOS. 1, 2, 5 and 6	9
TABLE 4. TREATABILITY DATA FROM THE FULL-SCALE TREATMENT	14

LIST OF FIGURES

FIGURE 1. SAMPLING LOCATIONS FOR CHARACTERIZATION OF BERM SOIL	3
FIGURE 2. RECOMMENDED FUTURE SAMPLE LOCATIONS	17

QUALITY INSPECTED B

Approved Date: _____ By: _____ Title: _____ Signature: _____
By Signature: _____ Title: _____ Signature: _____
A-1

FINAL REPORT

on

FIELD DEMONSTRATION OF A SIEVING AND STABILIZATION TECHNOLOGY ON LEAD-CONTAMINATED SOILS AT A SMALL ARMS RANGE AT MAYPORT NAVAL AIR STATION

to

NAVAL CIVIL ENGINEERING LABORATORIES

February 11, 1991

1.0 INTRODUCTION

This study was conducted for the U.S. Naval Civil Engineering Laboratory (NCEL) in Port Hueneme, California to demonstrate and evaluate the effectiveness of a sieving and stabilization process in treating soils at the small arms range at Mayport Naval Air Station, Mayport, Florida. The U.S. Naval Civil Engineering Laboratory (NCEL) coordinates projects involving the storage, treatment, and disposal of hazardous waste, and decontamination of groundwater and soil at various sites on Naval bases and stations. The Comprehensive Environmental Response Compensation and Liability Act (CERCLA), the Superfund Amendments and Reauthorization Act (SARA), and the Resource Conservation and Recovery Act (RCRA) require the Navy to clean up hazardous wastes that have been released in the past and to minimize the amount of hazardous waste that is currently produced. Treatability tests and a field demonstration of the stabilization process were conducted by ToxCo, Inc., of Claremont, California. Battelle's responsibilities included serving as third party witness to the excavation and treatment activities, conducting chemical analyses of both the treated and untreated soils to evaluate the effectiveness of the stabilization treatment method, and writing the final report.

Lead (Pb) shot accumulates in small arms practice range berm soils and over time creates a safety hazard due to ricochet and a pollution hazard due to the possible release of lead into groundwater and other environmental pathways. Other metals of possible concern were copper (Cu) and zinc (Zn) from the brass coatings on the lead shot. The objective of this task was to demonstrate and evaluate the effectiveness of a sieving and stabilization process in treating soils at small arms ranges to temporarily eliminate

ricochet and hazardous waste characteristics (specifically, toxicity characteristic due to lead leaching).

Mayport Naval Air Stations small arms range was the subject of this study. The soil impact berm measures approximately 92 feet across and was between seven and seven-and-one-half feet in height. The slope of the berm measures 18 feet from the base to the top. Weapons discharged on this range include shot guns, M-14, M-16, M-60, 45-caliber pistol and 38-caliber pistol. The actual age of the range is unknown. Also, any past maintenance activities on the impact berm are uncertain, however, we were informed by the activity that soil had been added to the berm in the past.

2.0 SAMPLING AND ANALYSIS PROGRAM

To establish a baseline concentration for the three metals of concern (Pb, Cu, and Zn) in the soil before treatment, Battelle coordinated the collection and chemical analysis of 30 different berm soil samples and one blind replicate. These samples were obtained from six one-foot depth intervals from five different sampling points in the target butt. Exact sampling locations were determined in conjunction with Navy personnel during the field sampling (see Figure 1).

Three horizontal cores were collected at range position number four, one in the bullet pocket approximately 13 feet up the slope of the target butt, one at six feet up the slope, and another at 17 feet up the slope from the base of the target butt. A total of 18 samples were collected from position number four. Another horizontal core was collected in the bullet pocket area at range position number eight. It was collected approximately 13 feet from the base up the slope of the target butt. The final group of samples were collected at range position number six. A vertical core was made from the top of the soil berm approximately three feet in front of the base of the wooden backstop.

All samples were collected using a stainless steel sand auger and collected in one-foot intervals. Each one-foot interval represents one sample. Each one-foot interval of soil was placed in a non-metallic container and composited and then placed in an appropriate labeled sample container. Chain-of-custody forms were filled out for each sample and shipped with the samples to the laboratory for analysis.

SAMPLE LOCATIONS

(before excavation)




FIGURE 1. SAMPLING LOCATIONS FOR CHARACTERIZATION OF BERM SOIL

Battelle was responsible for performing the chemical analyses on the berm soil samples. Chemical analyses include total Cu, Pb, and Zn and Toxicity Characteristic Leaching Procedure (TCLP)-extractable Cu, Pb, and Zn. Six of the samples were analyzed for pH. A split from each sample collected was provided to the Navy.

3.0 TREATABILITY STUDY

The bench-scale treatment phase involved evaluating a soluble silicate- and cement-based process. ToxCo Inc. in Anaheim, California was provided with four grab samples from the subject small arms range by the Navy prior to the sampling discussed in the sampling and analysis program in Section 2.0. The purpose was to determine if the chemical fixation process could lower the soluble Pb concentration below the EPA threshold limits, thus rendering the soil nonhazardous. The soil samples were first screened to remove rocks and large bullet fragments. The untreated soil was sent to Truesdail Laboratories in Tustin, California to be tested for total and TCLP-soluble Cu and Pb levels. Lead exceeded its TCLP limit of 5.0 milligrams per liter, therefore the berm soil failed the TCLP test for Pb. Note that Cu is not a TCLP-metal, but was analyzed in conjunction with Pb for research purposes.

The silicate/cement treatment was applied to each soil sample, and the treated samples were then analyzed for TCLP Cu and Pb levels. The process used was: a) 250 grams of soil was placed in a large beaker; b) five grams of sodium silicate was added to the waste and mixed; c) a total of 70 grams of water along with a trace of detergent was added to the beaker and again mixed; and d) finally, 62½ grams of low alkaline cement were added to the waste and thoroughly mixed.

The results of the TCLP extraction showed that after treatment, the TCLP Pb concentrations were well below the TCLP limit of 5.0 milligrams per liter. The results are presented in Table 1. The physical characteristics of the treated material were similar to the starting material, and therefore it was concluded that the treated material would have suitable physical properties for re-use as berm soil without causing ricochet problems.

TABLE 1. BENCH-SCALE TEST DATA

Metal	<u>Total Metals Concentration Untreated Soil (mg/kg)</u>			
	Sample 1	Sample 2	Sample 3	Sample 4
Lead	2,120	25,900	6,600	4,390
Copper	87.3	410	255	163
<u>TCLP Metals Untreated Soil (mg/l)</u>				
Lead	154	661	519	133
Copper	2.4	0.3	2.4	2.5
<u>TCLP Metals Treated Soil (mg/l)</u>				
Lead	<0.1	<0.1	0.16	2.1
Copper	<0.1	0.14	0.17	0.17

4.0 FIELD DEMONSTRATION

4.1 Initial Soil Sampling

As indicated in Section 2.0, 30 different berm soil samples were collected and chemically analyzed before the excavation of the berm for treatment in order to provide a characterization of the extent of metals contamination in the berm. Figure 1 identifies sample locations. The results of the chemical analyses are presented in Table 2. All analytical tests were performed by Battelle in Columbus, Ohio.

4.2 Pilot Test Preparation

Before starting the pilot tests, Toxco constructed a sieve using 1/4" screen mesh and 2" x 6" wooden frame. The dimension of the sieve was approximately 8' x 8'. The sieve set at a 60 degree angle which would allow the bullets to roll off.

Next, a path approximately three-feet deep leading back to the berm was excavated. The path was necessary to allow the front-end loader and backhoe to pass under overhead framework which covered most of the range and extended into the side berm.

The berm was excavated with a front-end loader and backhoe. Approximately four to five feet of soil were removed from the face of the berm and transported to the sieve in a flat working area in front of the range. The soil was placed on the sieve by a front-end loader. Rakes and shovels were used to help clear the bullets off the screen. The 1/4" mesh became clogged, and a 1/2" mesh screen was tested. The 1/2" mesh screen rejected most of the bullets and rocks and was used to sieve the remaining soil. The sieved soil was then stockpiled on plastic. Six samples of sieved soil were analyzed for total and TCLP lead, copper, and zinc. Table 3 presents the results of these analyses.

TABLE 2. CHARACTERIZATION OF UNTREATED SOIL BERM FOR Pb, Cu, AND Zn

Sample Identification	Total Metal Concentration (mg/kg)				TCLP Metal Concentration (mg/l)			
	Pb	Cu	Zn	pH 1:1	Pb	Cu	Zn	pH of Extract
1-0-1	5,800	110	17	--	250	2.0	0.5	5.18
1-1-2	14,200	260	40	--	470	1.8	1.2	5.33
1-2-3	16,200	468	68	--	100	1.3	1.6	5.65
1-3-4	9,200	125	26	--	445	2.0	1.1	5.29
1-4-5	1,740	3,740	218	8.67	100	0.6	0.2	5.13
1-5-6	1,985	21	4	8.74	36	0.7	0.1	5.19
1-5-6 Dup.	280	13	3	--	--	--	--	--
2-0-1	42,400	65,000	4,200	--	720	0.5	3.6	5.38
2-1-2	34,600	1,200	180	--	450	0.7	4.1	5.43
2-2-3	4,000	320	56	--	285	7	1.9	5.34
2-3-4	8,200	348	59	--	70	4.8	1.6	5.70
2-4-5	3,450	60	14	8.66	200	2.0	0.4	5.18
2-5-6	40	4	2	8.83	4.0	0.1	<1	5.20
2-5-6 Dup.	44	4	2	--	--	--	--	--
3-0-1	2,500	30	2	--	28.5	0.2	<0.2	5.70
3-1-2	50	4	<2	--	0.9	0.04	<0.2	6.18
3-2-3	269	8.3	7.7	--	14	0.2	<0.1	6.07
3-3-4	11,500	230	40	--	48	0.8	1.1	5.75
3-4-5	9,400	72	19	--	150	1.0	0.5	5.61
3-5-6	470	13	5	8.53	165	0.4	0.2	5.40
3-5-6 Dup.	1,000	12	5	--	125	0.4	0.2	5.30
4-0-1	16,600	8,100	900	--	550	1.9	1.3	5.34
4-1-2	4,400	140	18	--	88.4	2.0	0.5	5.60
4-1-2 Dup.	4,800	150	20	--	91.9	2.1	0.7	5.64
4-2-3	38,800	132	28	--	107	1.9	0.6	5.90

TABLE 2. CHARACTERIZATION OF UNTREATED SOIL BERM FOR Pb, Cu, AND Zn (Continued)

Sample Identification	Total Metal Concentration (mg/kg)				TCLP Metal Concentration (mg/L)			
	Pb	Cu	Zn	pH 1:1	Pb	Cu	Zn	pH of Extract
4-2-3 Dup.	6,580	118	26	--	--	--	--	--
4-3-4	2,490	126	32	--	90	0.9	0.6	5.56
4-4-5	10,600	660	72	--	100	0.9	0.4	5.65
4-5-6	4,530	2,380	237	8.40	235	1.0	0.4	5.30
4-5-6 Dup.	3,150	80	21	--	--	--	--	--
5-0-1	16,000	220	26	--	104	1.4	0.6	5.66
5-1-2	15,000	90	12	--	220	0.8	0.2	5.49
5-2-3	370	10	<2	--	30.1	0.2	<0.2	5.34
5-3-4	1,460	14	<2	--	36.7	0.3	<0.2	5.28
5-4-5	790	300	27	--	85.4	0.5	<0.2	5.50
5-5-6	940	10	<2	--	53.9	0.5	0.4	5.29
5-5-6 Dup.	325	20	<2	--	62.1	0.3	<0.2	5.21

Note on Sample Identification
 1st digit is sample location
 2nd and 3rd digits are the depth interval in feet.

TABLE 3. TREATABILITY DATA ON PILOT TEST RUNS NOS. 1, 2, 5, and 6

Sample Identification	Total Metal Concentration (mg/kg)				ICLP Metal Concentration (mg/L)			
	Pb	Cu	Zn	pH 1:1	Pb	Cu	Zn	pH of Extract
<u>Sieved Soil - Untreated</u>								
1-S	23,500	10,400	1,180	8.51	689	3.2	2.7	5.21
2-S	7,950	325	50	8.48	409	3.2	1.5	5.34
3-S	24,800	170	25	8.40	284	1.8	1.2	5.42
4-S	26,100	300	65	8.51	384	3.6	1.6	5.38
5-S	8,300	215	80	8.20	268	2.5	0.8	5.35
6-S	7,250	2,400	280	8.32	326	4.7	1.2	5.30
6-S Dup.	6,350	270	45	--	334	4.2	1.4	5.35
<u>Pilot Test No. 1</u>								
1-PT	15,620	6,520	660	12.51	<.5	<.1	<.1	9.95
2-PT	36,000	380	57	12.34	495	3.6	2.0	5.05
3-PT	9,300	295	43	12.52	1.0	0.1	<.1	8.01
4-PT	31,800	292	46	12.59	150	1.6	1.6	6.20
4-PT Dup.	35,800	2,750	315	--	160	1.8	1.0	6.21
<u>Pilot Test No. 2</u>								
1-PT-2	3,500	100	26	12.58	<.5	<.1	<.1	8.73
2-PT-2	2,600	95	25	12.61	<.5	<.1	<.1	10.95
3-PT-2	6,000	80	26	12.63	<.5	<.1	<.1	11.68
3-PT-2 Dup.	11,800	85	200	--	<.5	<.1	<.1	11.68

TABLE 3. TREATABILITY DATA ON PILOT TEST RUNS NOS. 1, 2, 5, and 6 (Continued)

Sample Identification	Total Metal Concentration (mg/kg)			ICLP Metal Concentration (mg/L)			
	Pb	Cu	Zn	pH 1:1	Pb	Cu	Zn
Pilot Test No. 5							
** 1-PT-3	3,950	150	140	12.13	0.5	--	--
* 2-PT-3	11,400	130	130	12.60	0.5	--	--
* 3-PT-3	13,500	130	130	12.63	0.5	--	--
Pilot Test No. 6							
** 1-PT-4	2,750	88	91	11.91	1.4	--	--
* 2-PT-4	3,700	120	130	12.62	1.3	--	--
2-PT-4 Dup.	--	--	--	--	1.4	--	--
* 3-PT-4	2,850	100	100	12.59	1.4	--	--
* 1-PT-4 Dup.	--	--	--	12.51	--	--	--

* pH measurements taken approximately one month after treatment.

** pH measurements taken approximately five days after treatment.

4.3 Pilot Tests

The first pilot test was conducted on October 3, 1990. An approximately 20 cubic yard pile of sieved soil was spread out on plastic on a flat working area in front of the practice range. Water was sprayed on the soil and 55 gallons of sodium silicate were spread over the soil with the bucket of the front-end loader. A large rototiller was then passed over the soil to mix the ingredients. Ten thousand pounds of cement were then applied to the pile by a truck with a metered spray bar on the back. The cement was rototilled into the soil mixture, covered with plastic and allowed to cure overnight.

The rototiller was passed over the treated pile the next day to help break it up. Four samples were taken from the treated pile and analyzed for total and TCLP lead. The analytical results from this pilot test are presented in Table 3 (Pilot Test No. 1). Two of the four samples were above the EPA limit of 5 mg/l for lead. The product from the first pilot test which was conducted to be unsuccessful, was returned to the untreated pile for retreatment, and the area was cleaned up. The unsatisfactory results of the process was attributed to inadequate mixing using the rototiller.

On October 10, 1990 a second pilot test was conducted using a 20-yard capacity roll-off box as a container. First, a seal was placed around the door to prevent leaks. Next, two-and-a-half cubic yards of sieved soil were placed in the roll-off box. A calibrated pump was used to meter ten gallons of sodium silicate solution and 160 gallons of water into the box. The contents of the box were mixed together with a hand-maneuvered rototiller. Next, 1,500 pounds of cement and additional water were added and mixed by rototilling. The amount of cement was metered when discharged from the delivery truck. It took about two-and-a-half hours to treat two-and-a-half cubic yards of soil. The mixture was covered and allowed to cure overnight. Three samples were taken and analyzed for total and TCLP lead. The results are provided in Table 3 (Pilot Test No. 2). These results showed that the stabilization technology worked. However, the mixing process was concluded to be too time-consuming and not cost-effective. Also, the final mixture was hard and difficult to break up, and therefore not desirable for placement back in the berm because of possible ricochet.

On November 28, 1990 the third pilot test was performed. This test was designed to produce a mixture with 20 percent cement, by weight, but due to a mix-up in equipment rental the final mixture contained 60 percent cement. Approximately 2.4 yd³ of soil was conveyed into a cement truck containing 30 gallons of sodium silicate, 250 gallons of water and a cup of soap. The cement truck remained rotating throughout the whole process. The amount of soil was monitored by counting the number of 1/4 yd³ back-hoe buckets that were put onto the conveyor belt. The water was metered into the truck at the cement company, and the sodium silicate was metered using a calibrated pump. The first cement truck discharged its content, via a conveyor belt into a second cement truck containing 4400 pounds of cement and 300 gal of water. The cement and water were both added at the cement company. The mixture was discharged into a roll-off box and allowed to cure overnight. One sample was taken from this mixture and the TCLP Pb level was 1.83 mg/l. This mixture was too hard to re-use on the face of the berm. The large pieces were placed at the very bottom of the berm, below the line of fire.

The fourth pilot test was conducted later on November 28. It was designed to have a product with 25 percent by weight of cement but again due to the equipment rental mix-up, it actually yielded a product with 75 percent by weight of cement. The same cement truck process was used but the ingredient amounts were:

2.4 yd³ soil
30 gal silicate solution
5400 lb cement
500 gal water
1 cup soap

The TCLP Pb level was 1.4 mg/l. Again, the hardened material was placed at the bottom of the berm.

The fifth pilot test was conducted on November 29, 1990 and used the following amounts of ingredients:

7.2 yd³
30 gal silicate
4400 lb cement
500 gal water
1 cup soap

This mixture corresponds to approximately 20 percent by weight cement. After this mixture cured for 4 hours, the treated soil was mixed up with a backhoe to determine if it would be easier to remove from the roll-off box. This proved to be a very significant step in the pilot test, because the process yielded a treated material that was relatively soft and friable, similar to the untreated berm sand. TCLP data are included in Table 3 (Pilot Test No. 5).

The sixth pilot test was also performed on November 29, 1990 and produced a mixture with 25 percent cement. The ingredient amounts were:

- 7.2 yd³ soil
- 30 gal silicate
- 5400 lb cement
- 500 gal water
- 1 cup soap

Again, the set of the cement was destroyed by mixing the treated grit with a backhoe approximately 4 hours into curing. The analytical results are presented in Table 3.

Because the TCLP results for Pb from the fifth and sixth pilot tests were well below the EPA limit of 5 mg/l, the process (No. 5) using 20 percent cement was selected for the full-scale treatment.

4.4 Full-Scale Treatment

On December 4, 1990 full-scale treatment began. As indicated, the full-scale treatment used the same process and amount of material as the fifth pilot test except with slight variations in the amount of water added to compensate for the variable water content of the berm soil. Also, the mixture was removed from the roll-off box and spread thinly after approximately four hours of curing. The next day it was broken up with the front-end loaders. A total of 12 treated soil samples were collected from the full-scale treatment and analyzed for total and TCLP Pb, Cu, and Zn. See Table 4 for analytical results. All of the samples passed the TCLP Pb criterion by a wide margin.

The treated soil was placed back on the face of the berm using a front end loader and backhoe. Next, a three- to four-inch layer of clean fill was placed over the treated soil on the berm so that the berm could be

TABLE 4. TREATABILITY DATA FROM THE FULL-SCALE TREATMENT

Sample Identification	Total Metal Concentration (mg/kg)				ICLIP Metal Concentration (mg/L)			
	Pb	Cu	Zn	pH 1:1	Pb	Cu	Zn	pH of Extract
1-T	14,100	120	110	12.62	<0.1	<0.05	<0.05	11.19
1-T Dup.	--	--	--	12.64	<0.1	<0.05	<0.05	11.24
2-T	4,000	110	110	12.59	<0.1	<0.1	<0.1	11.41
3-T	4,500	100	100	12.50	0.2	<0.1	<0.1	11.58
3-T Dup.	10,000	140	140	--	--	--	--	--
4-T	25,000	340	320	12.51	<0.1	<0.1	<0.1	11.50
5-T	9,000	110	120	12.40	<0.1	<0.1	<0.1	10.40
6-T	5,000	--	--	12.43	0.9	<0.1	<0.1	11.99
6-T Dup.	--	--	--	12.51	0.3	<0.1	<0.1	11.91
7-T	5,500	210	200	12.30	<0.1	0.1	0.2	11.53
8-T	20,000	120	130	12.31	<0.1	0.1	<0.1	11.52
9-T	14,000	2,400	2,200	12.32	<0.1	<0.1	<0.1	11.23
10-T	27,000	120	180	12.33	<0.1	<0.1	<0.1	11.20
11-T	13,500	210	210	12.32	<0.1	0.2	0.2	11.03
12-T	7,500	110	110	12.40	<0.1	0.1	0.1	11.59
12-T Dup.	4,000	1,200	1,100	12.41	<0.1	0.1	0.1	11.53

revegetated. The path to the berm was filled and the entire area was hydromulched with a native grass.

The material rejected by the sieve, comprising primarily of bullets, was turned over to the Mayport Morale, Welfare and Recreation Department, at their request, for recycling.

5.0 DISCUSSION AND CONCLUSIONS

5.1 Treatment Cost Analysis

The total cost of the Mayport Small Arms Range Stabilization project was \$130K. This included the cost of full-scale treatment (approximately 170 cubic yards), pilot test, mobilization, travel, excavation of the berm, replacement of treated soil on the berm, oversight, planning, and extensive sample analysis. The need for several pilot tests added to the overall cost. Because this was the first time this process was used in the field at a small arms range site, the costs are probably higher than what would be encountered for future projects.

5.2 Process Effectiveness

The stabilization process used in this project produced TCLP Pb values consistently below the EPA limit of 5.0 mg/l. The TCLP levels of the untreated soil were well above 250 mg/l, demonstrating that the stabilization process significantly reduced the leachable lead content.

The use of a 1/2" screen proved satisfactory in sieving out most of the bullets. For large projects, a vibrating screen with 1/2" openings is probably preferable. The vibrating screen would reduce the amount of labor and time needed for sieving, however, dust suppression will likely be necessary.

The use of cement trucks as the mixing device may be employed in projects of similar size, (<300 cubic yards) but a pugmill or similar mixing device with a higher throughput is recommended for larger projects.

5.3 Future Sampling

It is recommended that the berm be sampled once a year to monitor the TCLP Pb lead levels. These samples should be taken from locations each year. Proposed sample locations are illustrated in Figure 2.

Sample location No. 1 is located on the far left side of the berm away from direct fire. One sample should be taken three feet into the berm.

Sample location No. 2 is located in the middle of a bullet pocket. One sample should be taken from three inches below the surface of the berm. This sample will probably show very high levels of lead due to the direct fire.


Sample location No. 3 is located above sample location No. 2 but in the same firing line. One sample should be taken three inches below the surface of the berm.

Sample location No. 4 is located between two firing lines. One sample should be taken six inches below the surface of the berm.

All of the samples should be analyzed for total and TCLP Pb.

FUTURE SAMPLE LOCATIONS

(after treatment)



○ sample sites
samples taken once a year

FIGURE 2. RECOMMENDED FUTURE SAMPLE LOCATIONS

DISTRIBUTION QUESTIONNAIRE

The Naval Civil Engineering Laboratory is revising its primary distribution lists.

SUBJECT CATEGORIES

1 SHORE FACILITIES

- 1A Construction methods and materials (including corrosion control, coatings)
- 1B Waterfront structures (maintenance/deterioration control)
- 1C Utilities (including power conditioning)
- 1D Explosives safety
- 1E Aviation Engineering Test Facilities
- 1F Fire prevention and control
- 1G Antenna technology
- 1H Structural analysis and design (including numerical and computer techniques)
- 1J Protective construction (including hardened shelters, shock and vibration studies)
- 1K Soil/rock mechanics
- 1L Airfields and pavements
- 1M Physical security

2 ADVANCED BASE AND AMPHIBIOUS FACILITIES

- 2A Base facilities (including shelters, power generation, water supplies)
- 2B Expedient roads/airfields/bridges
- 2C Over-the-beach operations (including breakwaters, wave forces)
- 2D POW storage, transfer, and distribution
- 2E Polar engineering

3 ENERGY/POWER GENERATION

- 3A Thermal conservation (thermal engineering of buildings, HVAC systems, energy loss measurement, power generation)
- 3B Controls and electrical conservation (electrical systems, energy monitoring and control systems)
- 3C Fuel flexibility (liquid fuels, coal utilization, energy from solid waste)

- 3D Alternate energy source (geothermal power, photovoltaic power systems, solar systems, wind systems, energy storage systems)

- 3E Site data and systems integration (energy resource data, integrating energy systems)

- 3F EMCS design

4 ENVIRONMENTAL PROTECTION

- 4A Solid waste management
- 4B Hazardous/toxic materials management
- 4C Wastewater management and sanitary engineering
- 4D Oil pollution removal and recovery
- 4E Air pollution
- 4F Noise abatement

5 OCEAN ENGINEERING

- 5A Seafloor soils and foundations
- 5B Seafloor construction systems and operations (including diver and manipulator tools)
- 5C Undersea structures and materials
- 5D Anchors and moorings
- 5E Undersea power systems, electromechanical cables, and connectors
- 5F Pressure vessel facilities
- 5G Physical environment (including site surveying)
- 5H Ocean-based concrete structures
- 5J Hyperbaric chambers
- 5K Undersea cable dynamics

ARMY FEAP

- BDG Shore Facilities
- NRG Energy
- ENV Environmental/Natural Responses
- MGT Management
- PRR Pavements/Railroads

TYPES OF DOCUMENTS

D - Techdata Sheets; R - Technical Reports and Technical Notes; G - NCEL Guides and Abstracts; I - Index to TDS; U - User Guides; ☐ None - remove my name

Old Address:

Telephone No.: _____

New Address:

Telephone No.: _____

INSTRUCTIONS

The Naval Civil Engineering Laboratory has revised its primary distribution lists. To help us verify our records and update our data base, please do the following:

- Add - circle number on list
- Remove my name from all your lists - check box on list.
- Change my address - line out incorrect line and write in correction
(DO NOT REMOVE LABEL).
- Number of copies should be entered after the title of the subject categories you select.
- Are we sending you the correct type of document? If not, circle the type(s) of document(s) you want to receive listed on the back of this card

Fold on line, staple, and drop in mail.

DEPARTMENT OF THE NAVY
Naval Civil Engineering Laboratory
560 Laboratory Drive
Port Hueneme, CA 93043-4328

Official Business
Penalty for Private Use, \$300

BUSINESS REPLY CARD

FIRST CLASS PERMIT NO. 12503 WASH D.C.

POSTAGE WILL BE PAID BY ADDRESSEE

NO POSTAGE
NECESSARY
IF MAILED
IN THE
UNITED STATES

COMMANDING OFFICER
CODE L34
560 LABORATORY DRIVE
NAVAL CIVIL ENGINEERING LABORATORY
PORT HUENEME CA 93043-4328

NCEL DOCUMENT EVALUATION

You are number one with us; how do we rate with you?

We at NCEL want to provide you our customer the best possible reports but we need your help. Therefore, I ask you to please take the time from your busy schedule to fill out this questionnaire. Your response will assist us in providing the best reports possible for our users. I wish to thank you in advance for your assistance. I assure you that the information you provide will help us to be more responsive to your future needs.

R. N. Storer

R. N. STORER, Ph.D., P.E.
Technical Director

DOCUMENT NO. _____ TITLE OF DOCUMENT: _____

Date: _____ Respondent Organization: _____

Name: _____ Activity Code: _____

Phone: _____ Grade/Rank: _____

Category (please check):

Sponsor _____ User _____ Proponent _____ Other (Specify) _____

Please answer on your behalf only; not on your organization's. Please check (use an X) only the block that most closely describes your attitude or feeling toward that statement:

SA Strongly Agree A Agree O Neutral D Disagree SD Strongly Disagree

	SA	A	O	D	SD		SA	A	O	D	SD
1. The technical quality of the report is comparable to most of my other sources of technical information.	()	()	()	()	()	6. The conclusions and recommendations are clear and directly supported by the contents of the report.	()	()	()	()	()
2. The report will make significant improvements in the cost and or performance of my operation.	()	()	()	()	()	7. The graphics, tables, and photographs are well done.	()	()	()	()	()
3. The report acknowledges related work accomplished by others.	()	()	()	()	()	<div style="border: 1px solid black; padding: 5px; display: inline-block;"><p>Do you wish to continue getting NCEL reports? <input type="checkbox"/> YES <input type="checkbox"/> NO</p></div> <p>Please add any comments (e.g., in what ways can we improve the quality of our reports?) on the back of this form.</p>					
4. The report is well formatted.	()	()	()	()	()						
5. The report is clearly written.	()	()	()	()	()						

Comments:

Fold on line, staple, and drop in mail.

DEPARTMENT OF THE NAVY
Naval Civil Engineering Laboratory
560 Laboratory Drive
Port Hueneme CA 93043-4328

Official Business
Penalty for Private Use, \$300

BUSINESS REPLY CARD

FIRST CLASS PERMIT NO. 12503 WASH D.C.

POSTAGE WILL BE PAID BY ADDRESSEE

NO POSTAGE
NECESSARY
IF MAILED
IN THE
UNITED STATES

COMMANDING OFFICER
CODE L03
560 LABORATORY DRIVE
NAVAL CIVIL ENGINEERING LABORATORY
PORT HUENEME CA 93043-4328